


ARCH-TOP HEADBOARD

MATERIALS


A Post Faces (4)	$\frac{3}{4}$ x $3\frac{1}{2}$ - 54 rgh.	I Outer Stiles (2)	1 x 3 - $24\frac{1}{2}$
B Post Sides (4)	1 x $2\frac{3}{4}$ - 54 rgh.	J Splines	$\frac{1}{2}$ x 1 - 32 In. ft.
C Filler Strips	$\frac{1}{2}$ x $\frac{1}{2}$ - 32 rgh.	K Inner Stiles (2)	1 x $3\frac{1}{2}$ - 30 rgh.
D Ogee Trim Plates (6)	$\frac{3}{4}$ x 5 - 5	L Center Panel (1)	$\frac{3}{4}$ x 24 - 31 rgh.
E Bullnose Trim Plates (4)	$\frac{3}{4}$ x $5\frac{5}{8}$ - $5\frac{5}{8}$	M Outer Panels (2)	$\frac{3}{4}$ x 11 - 28 rgh.
F Top Rail (1)	1 x 12 rgh. - 56	N Back Panel (1)	$\frac{1}{4}$ ply. - 30 x 51
G Bottom Rail (1)	1 x 8 - 56		
H Molding (1)	1 x $7\frac{3}{8}$ rgh. - 56		

CUTTING DIAGRAM


1" x $7\frac{1}{2}$ " - 96" Cherry (Two Boards @ 7.5 Bd. Ft. Each)



$\frac{3}{4}$ " x $7\frac{1}{2}$ " - 96" Cherry (Two Boards @ 5 Bd. Ft. Each)




$\frac{3}{4}$ " x $6\frac{1}{2}$ " - 96" Cherry (Two Boards @ 4.3 Bd. Ft. Each)



1" x $7\frac{1}{2}$ " - 96" Cherry (7.5 Bd. Ft.)




$\frac{3}{4}$ " x 6" - 60" Cherry (2.5 Bd. Ft.)



1" x 6" - 60" Cherry (Two Boards @ 3.12 Bd. Ft. Each)



1" x $8\frac{1}{2}$ " - 60" Cherry (4.2 Bd. Ft.)



C & J
Spline and filler
pieces are cut
from this section

SUPPLIES

- (16) #8 x $2\frac{1}{2}$ " Fh Woodscrews
- (40) #8 x 1" Rh Woodscrews
- (16) #6 x $\frac{1}{2}$ " Rh Woodscrews
- (4) $\frac{1}{4}$ " -20 Threaded Inserts
- (4) $\frac{1}{4}$ " -20 x 1" Hex Head Screws
- (4) $\frac{1}{4}$ " Washers

